SECTION 71

STREETS

- 71-1 GENERAL Street surface improvements shall include: barricades, bikeways, bridges, bollards, curb, curb & gutter, driveways, pavement, curb ramps, sidewalk, survey monuments and tunnels. These improvements shall be installed in accordance with the approved improvement plans, these Construction Standards and the latest edition of The State of California Department of Transportation Standard Specifications hereinafter referred to as the Caltrans Standard Specifications latest edition and as specified by the City Engineer. No Street shall be cut, nor any public improvement disturbed until the Developer/Contractor has obtained an encroachment permit from, and/or entered into a subdivision agreement with the City.
- **71-2 CONNECTION TO EXISTING IMPROVEMENTS** Connection to existing surface improvements require that the following conditions be met:
 - **A. Existing Stub Street Connection** The Developer shall be responsible for removing and reconstructing a portion of the existing roadway to make a satisfactory connection, as required by the City Engineer.
 - **B. Street Widening** When widening to complete a partial street along a development project, the Developer shall be responsible for saw cutting and removing a narrow strip along the outside portion of the pavement to provide a clean and stable pavement section for constructing against. The width from centerline shall be shown on the approved plans or as determined in the field, and verified by the City Engineer. Following construction of the adjacent curb and gutter, paving shall not commence until the City's Construction Inspector is satisfied that the cross grade between the existing pavement edge and the new gutter lip conforms to or approaches the City's required 2% cross grade. 3% is the maximum cross grade allowed on this AC pavement section unless shown on the approved plans.
 - **C. Sawcutting** When sawcutting within the street for trenching or other purposes, Contractor shall grind 1-1/2 inches of pavement between the lane lines (from lane stripe to lane stripe), upon completion of the sawcutting and/or trenching work. Where the sawcutting occurs between the curb and gutter and nearest lane stripe (including bike lanes), the same 1-1/2 grind shall be required. Contractor to place a Petromat fabric or approved equal by the City, and overlay from lane stripe to lane stripe, or curb to lane stripe and restripe or replace any delineators removed during the grind.

71-3 **CONSTRUCTION STAKING** - Construction staking shall be provided by the Developer for all surface improvements. Such staking shall provide the station and offset, as well as the cut to the nearest hundredth (0.01) of a foot. Stakes shall be provided at a minimum of every 50 feet in tangent sections and every 25 feet in curved sections. Monuments shall have straddle ties placed.

Cut sheets for the appropriate phase of work shall be on-site and shall be furnished to the City's Construction Inspector upon request.

The engineer's surveyor shall stake the grades and location for the top and bottom of slope for all curb ramps.

71-4 INSTALLATION

A. Subgrade - **Note:** The geotechnical engineer shall closely monitor and test subgrade fills to assure the material meets soil R-Values identified in the street design portion of the project soils report. If R-Values differ from the soils report, structural sections shall be adjusted (including plan revisions) by the design engineer and approved by the City Engineer. Where mehrten (mehrten mudflow breccia and /or mehrten conglomerate), lava cap material, cobbles or other stable native subgrade materials are encountered upon commencement of street grading, the respective material may be substituted for processed subgrade, and/or aggregate subbase and /or aggregate base. This is conditional upon confirmation by the geotechnical and design engineers (and approval of the City Engineer) that the existing subgrade/subbase/base section thicknesses and composition will meet or exceed traffic index and R-Value requirements for the respective street. A minimum of three inches of Class II aggregate base shall be required on such substituted material on which to pave.

Soils testing for relative compaction shall reference ASTM D1557-78 test methods.

1. Subgrade for Sidewalk and Curb Ramps, Curb and Gutter, Driveways and Asphalt Concrete Paving - Subgrade shall be processed to 95% relative compaction, minimum six inches plus, and shall be tested and certified by a geotechnical engineer, licensed in California. Written certification shall be provided to the City's Construction Inspector prior to the placement of concrete (and aggregate base or aggregate subbase for asphalt concrete). For meandering sidewalks, Class II aggregate base may be substituted for native subgrade at the Contractor's discretion and shall be processed to 95 % relative compaction.

Additionally, subgrade stability for curb, gutter and sidewalk and asphalt concrete pavement shall be load tested by proof rolling with a loaded, minimum 3,000 gallon water truck (or equipment of equivalent weight as approved by the City's Construction Inspector) in the presence of the City's Construction Inspector, the Geotechnical Engineer and the Contractor. The proof roll test shall be repeated following corrective measures. Prior to placement of aggregate base, deflection in the subgrade shall be eliminated. Placement of aggregate base shall not commence without the approval of the City's Construction Inspector.

Where mehrten (mehrten mudflow breccia and/or mehrten conglomerate), lava cap material, cobbles or other native subgrade material not conducive to the operation of the concrete extruding machine are encountered, that material shall be removed to a depth of six inches below top of subgrade, and shall be replaced with native or imported soil (acceptable to the City's Construction Inspector and the geotechnical engineer) compacted as specified above.

Aggregate base is not included in the structural section for monolithic sidewalk and Type 1 (or Type 2) curb and gutter. Aggregate base may be used for meandering or otherwise detached sidewalk.

Sidewalk subgrade exposed upon removal of existing sidewalk shall remain intact unless it is determined by the City's Construction Inspector to be unstable. In this event, it shall be processed per the preceding paragraphs.

Deflecting, unstable areas shall be corrected per the recommendation of the Geotechnical Engineer and upon the approval of the City's Construction Inspector prior to placement of aggregate base, or concrete curb, gutter and sidewalk.

ORDER OF WORK: Street subgrade preparation, concrete placement and placement of any aggregate base or subbase for asphalt concrete pavement within the City right-of-way shall conform to the following sequence of operations, not withstanding Section B. below. Prior to placement of aggregate base in the City right-of-way, the contractor shall:

- a. Complete underground work outlined in Section B, below.
- **b.** Process and compact subgrade for curb, gutter, sidewalk and asphalt concrete pavement, back of sidewalk to back of sidewalk.

- **c.** Complete construction of curb, gutter and sidewalk after approval of the subgrade by the City's Construction Inspector.
- **d.** In addition to Section 90-8 Protecting Concrete, the Contractor shall protect newly placed concrete finish from rainy conditions, graffiti, and weather related damage. In addition, all Contractor wheeled equipment shall not travel within one foot of the lip of gutter in the first 24 hours following concrete placement. Contractor's vibratory compaction equipment may not operate within 72 hours and until all adjacent sidewalk, curb and gutter concrete has reached a minimum of 1400 psi compressive strength.
- **e.** Complete finish grading of subgrade for asphalitic concrete pavement, conduct proof rolling test and begin placement of aggregate subbase and/or aggregate base after approval of the finished subgrade by the City's Construction Inspector.
- **B. Aggregate Base and Subbase** Roadway aggregate base and subbase, lime/cement treated base and sidewalk, curb and gutter shall not be placed until the following items of construction within the City street right-of-way are completed:
 - 1. Installation of underground sewer and water systems and testing or televising, and approval of same by the EUD Inspector.
 - Completion of testing for the presence of bacteria and the water system tie-in shall not be requirements for the approval of commencement of surface improvement construction. However, the water main tie-in shall be completed prior to asphalt concrete paving. The Contractor shall schedule operations such that the curb, gutter and sidewalk pour shall not be conducted on the same day as the water tie-in.
 - **2.** Installation and mandrelling of the non-rigid underground storm drain pipe and approval of same by the City's Construction Inspector.
 - **3.** Installation of electric, natural gas, telephone, traffic signal (including interconnect) and cable TV, including mandrelling and testing of all conduits, installation of 4x4 markers a minimum of two feet high, painted red, buried at the crossing ends (if conduit ends do not extend up from finish grade). This includes all dry utility crossing and longitudinal trenches.

4. Backfill and compaction testing of all trenches related to the above and approval of same by the City's Construction Inspector.

All aggregate base and subbase (AB and ASB) shall be installed per provisions in Sections 25 and 26 of the Caltrans Standard Specifications. AB and ASB shall be compacted to 95% relative compaction. An oil seal is not required on the AB surface. If required by the City's Construction Inspector, AB and ASB shall be tested for compaction and approved by geotechnical engineer, licensed in California. It shall be proof rolled as specified in Section 71-4A.1 above if requested by the City's Construction Inspector. Written certification of compliance to these requirements shall be provided to the City's Construction Inspector.

Aggregate base shall be installed as a base for asphalt concrete paving where specified on the approved plans including over lime and fly ash or cement treatment is used.

Aggregate base in any thickness determined by the contractor may be used for meandering sidewalk wherever that sidewalk is not connected to the back of curb, or as a base for A-7 driveways outside the sidewalk at the curb returns. All aggregate base shall be compacted to 95%.

Where lone valley gutters are placed within the City pavement as in an alley, the aggregate base section for the gutter shall extend to the same depth as the aggregate base section for the adjacent asphalt concrete pavement.

Prior to paving, deflection in the compacted aggregate base shall be eliminated. Paving shall not commence without the approval of the City's Construction Inspector.

Lime/fly ash or other base stabilizers may be substituted for aggregate base as permitted in Section 71-5 D, Materials, Provided a sacrificial two (2) inch thick layer of aggregate base is placed beneath the base lift of asphalt concrete, and compacted to 95% relative compaction. The City following addition and processing of lime/flyash or cement shall inspect all manholes. If residue is found in the system, the Environmental Utilities or City's Construction Inspector will require further testing or televising at their discretion and sewer or storm drain systems shall be cleaned as appropriate. In the event a dig up and repair is required following lime/cement treatment; the entire excavation shall be backfilled with two-sack cement slurry, conforming to the Construction Standards.

C. Concrete - All concrete curbs, curb & gutters, sidewalks, curb ramps, driveways, bus stop pads and turnouts shall be installed per provisions

in Section 73 of the Caltrans Standard Specifications, Construction Standard Details ST-17 through ST-30 and ST-35 and ST-37 including the following provisions:

1. **Thickness** - All residential and commercial sidewalks shall be either six" thick, or 4" thick with 4" of compacted aggregate base. Across commercial driveways, and round-a-bout centers the concrete section shall be eight (8") inches with grade 60, #4 rebar, and 18 inches on center each way, conforming to the Construction Standard Details.

All commercial driveways and bus turnouts shall be eight (8") inches thick, with number 4, grade 60 rebar, on 18-inch centers each way. Rebar shall be set on 3 inch concrete dobies/rebar supports at three foot maximum spacing each way. The dobies shall include wire ties. See the Construction Standard Details.

Base for commercial driveways may be processed native subgrade or 3/4 –inch aggregate base compacted to 95% relative compaction.

2. Finishing - Concrete shall not be placed or finished in the rain. It shall be the Contractor's responsibility to schedule construction operations accordingly.

All gutters shall be flow tested with water during the pour to assure proper drainage. Following concrete finishing, no water shall pond in the gutter pan.

All concrete surfaces shall be completed with a medium broom finish unless otherwise specified. A heavy broom finish is not allowed. A concrete finish not conforming to the Caltrans Standard Specifications with regard to blemishes and alignment tolerances shall be cause for rejection of the work.

No stamps advertising construction companies or other private concerns shall be placed in the concrete.

A detectable warning (truncated dome) panel shall be placed at the back of curb line, immediately behind the curb and gutter, centered in the opening to the street (regardless of slope) at every curb ramp. (and shall not be sized as shown on the Case C ramp on Caltrans Standard Plan RNSP A88A) The panel shall consist of a one piece, four foot by three-foot panel. The four-foot dimensions of the panel shall be along the face of curb. The top, flat, done panel surface (excluding the domes) shall be placed flush with the adjacent top of concrete surface.

Any runoff water standing behind the curb on the panel, or concrete voids under the panel shall be cause for replacement of the panel. See Section 71-5 (Materials).

3. Tool joints and score marks - Tool joints and score marks shall be placed through the sidewalk, curb and gutter section at the following intervals for the sidewalk widths indicated. All tool joints shall be a minimum two inches. There shall be no expansion joint material used in the City right-of-way.

The purpose of the tool joint is to separate the aggregate and control cracking. During concrete finishing, after placement of a

minimum two-inch deep tool joint, the joint shall be readdressed/finished with a 3/8-inch joint tool, per Detail ST-17.

Sidewalk	Deep Tool	Score Mark
Width	Spacing	Spacing
(ft.)	(ft.)	(ft.)
4	12	4
5	10	5
6	12	6
8	12	6
10	10	n/a

A score mark shall be placed at the back of the curb for the total length of all monolithic curb, gutter and sidewalk including through curb ramps and driveways. The above intervals for perpendicular score marks in sidewalk shall also apply through curb ramps and driveways.

All barrier curb and valley gutters shall include deep tool joints at 12-foot intervals maximum.

The use of sawcutting in lieu of deep tool joints is not acceptable.

4. Grades - All sidewalks (including portions through driveways and curb ramps) shall be constructed with a minimum crossgrade of 1% and a maximum of 2%.

Parallel to the street, the grade of the curb ramp landing shall conform to the longitudinal grade of the street.

For all curb ramps the maximum of 8.33%.

For the ramp to the lower side of the landing, (where the ramp must be shortened to achieve the minimum 7% grade), four feet shall be the minimum length transition allowed.

For meandering sidewalks, the maximum grade in the direction of travel shall be 5% if the street grade allows. If the longitudinal street grade exceeds 5%, the curb side of the meandering sidewalk shall parallel the grade of the back of curb, maintaining a grade of 2% from the edge of sidewalk to the back of curb. For all meandering sidewalks, a minimum crossgrade of 2% shall be maintained from the edge of sidewalk, across the planter to the back of curb. Where curb ramp landings adjoin the back of curb, the top of curb shall be sloped up from the gutter flowline 1.0 to 2% to the back of landing for Type 1 and Type 2, curb and gutter. See Detail ST-22.

Gutter slope from lip to flowline shall be 5% conforming to Detail ST-17.

The preceding slope specification conform to ADA, California Division of the State Architect, and Caltrans Standard Specification requirements. Any finished concrete not conforming to theses slope specification shall be removed and replaced by and at the expense of the contractor.

- **5. Monolithic sidewalk, curb and gutter** All adjoining sidewalk, curb and gutter shall be poured monolithically.
- **6. Curb and gutter installation in an existing street** In an existing street, a minimum width of 24 inches of existing asphalt concrete paving shall be removed outside the proposed gutter lip and the lip poured against a form board. The resulting patch between the gutter lip and the existing pavement shall be six inches thick minimum, or the thickness of the existing pavement, whichever is greater. The AC patch shall be placed within two weeks of the conclusion of the concrete pour.

The minimum waiting period for pavement patching is three days from the date of placement or, the length of time needed for the concrete to reach 80% of its required ultimate strength, whichever is more. The gutter may be placed against the existing pavement if the City's Construction Inspector determines the pavement edge is flawless. In this case, the gutter lip shall not be edged and shall be poured ½ inch below the existing pavement.

7. Curb Ramps, General - See Details ST-22, ST-26, and ST-27. Other ramp configurations in the Caltrans Standard Plans may be

used upon the pre-approval of the City Engineer only if site conditions prohibit use of Roseville's standard ramps.

All grade changes at the back of walk for curb ramps shall be staked by a licensed surveyor, conforming to these Construction Standards.

Specifications for curb ramps in the Construction Standards take precedence over the Caltrans Standard Plans and Specifications. Where there are discrepancies between details shown on the approval plan sheets and the Construction Standards, the plans shall be revised to conform to the Construction Standards unless specifically approved by the City Engineer.

- **8. Epoxy Work** Epoxy shall be liberally applied to a minimum of 95% of one of the existing surfaces to be connected. Epoxy shall be two part and conform to Section 71-5 (Materials).
- **9. No Sidewalk at Back of Retaining Curb** At any curb ramp, no pedestrian surface (i.e., concrete, asphalt concrete, paving stones, etc.) adjacent to the back of sidewalk, shall be constructed within 3 feet behind the retaining curb. This area shall be finished with landscaping, cobbles or other non-pedestrian surface only. If the occasion arises wherein the City Engineer determines that placing concrete behind the retaining curb is justified, the top and face of the retaining curb shall be painted yellow.
- 10. Curb, Gutter and Sidewalk Patching Patch material shall conform to Section 71-5 (Materials). A professional concrete mason shall apply the patch. The patch shall be flush with the existing concrete and a similar finish shall be maintained. The City's Construction Inspector shall determine if the damage to the concrete warrants patching. Generally, any conspicuous damage shall be patched.
- 11.Dowling New Concrete to Existing When pouring combinations of sidewalk or curb and gutter contiguous to existing, the existing concrete vertical face shall be doweled three feet on center with 16 inch long, grade 60, #4 rebar penetrating four inches into the existing curb, four inches below top of curb. The dowel hole shall be 5/8-inch diameter at a slight angle horizontally. The penetrating portion of the dowel and the entire cleaned vertical surface of the adjoining existing concrete shall be 95% coated with two-part epoxy. All abutting sidewalk shall be doweled mid-section with two dowels for four through six-foot wide sidewalk and three dowels for wider sidewalk. Abutting curb and gutter ends shall be

doweled twice, 18 inches apart, centered on the curb and gutter section. See Section 71-5 (Materials) for epoxy.

Where the street side of the meandering sidewalk meets the back of Curb at less than a 90 degree angle, the return to the back of curb shall be a minimum 18 inch radius or 18 inch space shall be provided between the front face of sidewalk and the back of curb.

Replaced sections shall be removed back to score marks, expansion joints or deep tool joints; or at the discretion of the City's Construction Inspector.

If the existing edge is damaged during removal, the concrete shall be sawcut again at the City's Construction Inspector's discretion.

- 12. Sidewalk, curb and Gutter Replacement Where sidewalk and/or curb and gutter is being replaced, the maximum length of sidewalk that may be replaced non-monolithically (without the attached curb and gutter) is 20 feet. If more than 20 feet is damaged continuous, the total sidewalk, curb and gutter section shall be removed and replaced monolithically. Where sidewalk, curb and gutter or curb ramps and driveways with sidewalk, curb and gutter as portions thereof are replaced, all replacement shall conform to the latest Construction Standards.
- **13. Median Islands** All new roadway median infill areas shall have basket weave pattern stamped concrete with brick red #1117 per Detail ST-37. Existing cobble medians in retrofit areas effected by utility cuts or damage will be replaced per the following:

Cobbles set in four inches of pea gravel concrete. The top surface of the concrete shall be flush with the top of curb. Where cobble demolition within a median amounts to 50% of the area or more, all existing cobbles to be removed and replaced with "Ashler Slate" per Detail ST-37, and at the applicant's expense.

Cobbles shall be four to six inches in size, with 1/3 exposed above the top of curb, per Caltrans Specifications. Base for concrete may be native soil compacted to 95% or Class II, 3/4 inch aggregate base. On existing pavement, the two acceptable alternatives for base are 3/4 – inch aggregate base or total depth concrete. The surface of all embedment concrete shall be above the top of curb and graded/finished to drain.

Existing Grey stamped medians in retrofit areas effected by Utility cuts will be replaced per the following: Gray stamped concrete retrofit areas effected as described above shall be replaced in-kind

with, four inches thick "Ashler Slate" and standard color shall be basalt gray (QC Release Power Colors).

- **14. Damaged Gutter Lip** Gutter lip damaged during the grading and rocking operation shall be patched or replaced per Section 71-5, G.below. Any spall extending more than one inch into the gutter pan from the vertical face of the gutter lip shall be patched at a minimum. See Section 71-5, Materials.
- **15. Concrete and Asphalt Concrete Saw Cutting** Residual from sawcutting shall be removed by vacuum method and disposed of conforming to local environmental and State Stormwater Pollution Prevention Plan requirements. The down stream drain inlet shall be protected. In no case shall the residual be allowed to enter the storm drain system. The above-specified cleanup shall be the responsibility of the contractor.
- 16. Concrete Cure All newly placed concrete shall be cured in accordance with the provisions in Section 90-7.01B of the State Standard Specifications and these Construction Standards. See Section 71-5.I. (Materials) of these Standards for curing compound. Exposed surfaces of all concrete sidewalk, curb and gutter, driveways, but turnouts and curb ramps shall be coated with a pigmented curing compound immediately following surface finishing, prior to the moisture sheen disappearing from the surface. Curing compound shall be applied at a rate of one gallon per 150 square feet, or per the manufacturer's recommendations, whichever is greater, unless otherwise specified.
- **D. Asphalt Concrete Paving** All asphalt concrete (AC) shall be installed per provisions in Section 39 of the Caltrans Standard Specifications, except as amended by Section 71, "Streets", of the City Construction and Design Standards.

No paving shall occur until all underground work is completed and subgrade and/or aggregate base or lime and flyash or cement treated base have been accepted by the City's Construction Inspector.

1) **Mix Design** - The Contractor shall provide the asphalt concrete mix design to the Director of Development Services at least ten (10) working days prior to the start of the work on the project for review and approval. The mix design must be approved prior to commencement of work.

The asphalt concrete mix design shall indicate the following:

a) Complete aggregate grading with the percentage of aggregate

passing each sieve size.

- **b)** Percent air voids for each percentage of asphalt binder used in the mix design determination.
- **c)** Hveem Stability for each percentage of asphalt binder used in the mix design determination.
- **d)** Maximum theoretical density for each percentage of asphalt binder used in the mix design determination.
- **e)** Compacted unit weight for each percentage of asphalt binder used in the mix design determination.
- **f)** Percent asphalt binder recommended. (Optimum bitumen content, OBC).

The amount of asphalt binder (OBC) to be mixed with the aggregate for asphalt concrete will be recommended by the material supplier and approved by the Director of Development Services based on data from California Test Method CTM 367 provided by the Contractor. CTM 309 shall be used for determination of the theoretical maximum specific gravity at each asphalt binder content. However, the ratio for asphalt binder to the dry weight of aggregate shall be limited to 4 to 7 percent.

The actual asphalt cement content may vary up to 0.5% plus/minus form the target optimum bitumen content (OBC). At the OBC, the compacted mixture shall have a minimum Hveem stability of 37.

2) Spreading and Compaction Equipment - The first paragraph of Section 39-5.01, "Spreading Equipment" of the Caltrans Standard Specifications is amended to read:

"Asphalt concrete shall be spread with a self-propelled asphalt paving machine."

Asphalt concrete placed inlayers of 0.15-fot and greater in compacted thickness or widths of 5 feet and greater shall be spread and compacted with the equipment and by the methods specified in Section 39, except as amended as follows:

a. The entire contents of Section 39-5.02, "Compacting Equipment," of the Caltrans Standard Specifications are replaced to read:

"39-5.02 Compacting Equipment-The Contractor shall furnish a sufficient number of rollers to obtain the specified compaction and surface finish required by these Specifications.

Each roller shall have a separate operator. All rolling equipment shall be self-propelled and reversible.

All rollers shall be equipped with pads and water systems, which prevent sticking of asphalt mixtures to the pneumatic or steel-tired wheels. A parting agent, which will not damage the asphalt mixture, as determined by the Inspector, may be used to aid the preventing the sticking of the mixture to the wheels.

3) Compacting - The entire contents of Section 39-6-03, "Compacting," of the Caltrans Standard Specifications, is replaced to read:

As per Section 39-6-01, "General Requirements" of the Caltrans Standard Specifications, asphalt concrete shall be placed only when the atmospheric temperature is above 50 degrees Fahrenheit, unless otherwise approved by the City Engineer. Asphalt concrete shall be spread at a temperature of not less than 260 degrees F.

A pass shall be one movement of a roller in either direction. Coverage shall be as many passes as are necessary to cover the entire width being paved. Overlap between passes during any coverage, made to ensure compaction without displacement of material, and shall be considered to be part of the coverage being made and not part of a subsequent coverage. Each coverage shall be completed before subsequent coverage is started.

Rolling shall commence at the lower edge and shall progress toward the highest portion, except that when compacting layers which exceed 0.25-foot in compacted thickness, and if directed by the Inspector, rolling shall commence at the center and shall progress outwards.

Rolling shall be performed so that cracking, shoving, or displacement does not occur.

When placing asphalt concrete, large aggregate that migrated to the surface during any handwork shall be returned to the pave box, rather than scattered over the surface of the mat.

Finish rolling or final compaction shall be completed while the temperature of the mixture is at or above 150° F. A vibratory roller may be used as the finish roller provided it is operated with the vibratory unit turned off.

Upon completion of rolling operations, if ordered by the City City's Construction Inspector, the asphalt concrete shall be cooled by applying water. Applying water shall conform to the provisions in Section 17, "Watering of the Caltrans Standard Specifications."

Asphalt concrete shall be compacted to not less than 92 percent or more than 96 percent of the theoretical maximum density as determined by CTM 309 and shall be finished to the lines, grades, and cross section shown on the Project Plans.

The City Inspector reserves the right to gather samples for material testing at random for the hot mix asphalt (HMA) material from behind the paving machine in accordance with CTM 125 to determine the maximum theoretical density of the HMA mixture in accordance with CTM 309. The theoretical maximum density results derived from the samples shall be averaged and used to determine the relative density achieved for the shift.

The pavement will be accepted for density on a lot basis. A lot will consist of 1,000 tons or portions thereof. Cores for determining the density of the compacted pavement will be taken on a lot basis. A minimum of three (3) cores shall be taken per lot. The density of each core shall be determined in accordance with CTM 308.

The Contractor shall provide daily laboratory results of CTM 308 and CTM 309 to the City's Construction Inspector.

In-place pavement density will be determined by comparing the density of cores taken from the compacted pavement to the theoretical maximum density as determined by CTM 309. Pavement cores shall be collected using a 4 to 6 inch diameter core barrel when the pavement has cooled sufficiently to minimize disturbance to the cores at the discretion of the City's Construction Inspector.

Finish, compacted pavement height shall be ¼-inch above and over the gutter lip, except for six (6) feet at the curb ramp opening, where it shall be flush with the top surface of the gutter lip. Corrective operations for recently placed pavement more than ¼-inch above the gutter lip may include reheat, knead and re-compact with pneumatic tired rollers, in order to bring the improvements into compliance.

The horizontal surface of AC paved against an existing AC surface shall be flush with the existing surface.

The completed surfacing shall be thoroughly compacted, smooth and free from ruts, humps, depressions or irregularities. Any ridges, indentations or other objectionable marks left in the surface of the asphalt concrete by blading or other equipment shall be eliminated by rolling or other means approved by the Inspector. The use of any equipment that leaves ridges, indentions or other objectionable marks in the asphalt concrete shall be discontinued, and the Contractor shall furnish acceptable equipment.

Asphalt concrete placed in layers less than 0.15-foot in compacted thickness or widths of less than 5 feet shall be spread and compacted with equipment and by the methods specified in Section 39 of the CALTRANS Standard Specifications.

4) Miscellaneous Paving Requirements - When a straightedge 12 feet long is laid on the finished surface and parallel with the centerline, the surface shall not vary more than 0.01-feet from the lower edge of the straightedge. The transverse slope of the finished surface shall be uniform to a degree such that no depressions greater than 0.02-feet are present when tested with a straightedge 12 feet long laid in a direction transverse to the center line and extending from edge to edge of a 12-foot traffic lane.

If the finished surface of the asphalt concrete does not meet required surface tolerances, as specified above, the Contractor shall, at its own expense, bring pavement surface within tolerance by the following method:

- **a.** Cold plane asphalt pavement to a minimum depth of 0.15 feet from specified finish surface; (lateral limits shall be from edge of asphalt concrete to edge of asphalt concrete; longitudinal limits shall extend a minimum of 50 feet, starting from the outer edge of tolerance area and extending outward, and as directed by the Inspector). All grindings shall be removed and disposed of in accordance with Section 7-1.13, "Disposal of Material Outside the Highway Right-of-Way," of the Caltrans Standard Specifications.
- **b.** The Contractor shall apply tack coat and place an overlay of asphalt concrete in accordance with the requirements of the City Standard Specifications.
- **c.** The area to which asphalt emulsion has been applied shall be closed to public traffic. Care shall be taken to avoid tracking binder material onto existing pavement surfaces beyond the limits of construction.

Pavement within 50 feet of an approach to a bridge structure or approach slab shall conform to the smoothness tolerances specified in Section 51-1.17, "Finishing Bridge Decks", of the CALTRANS Standard Specifications."

The surface edges that abut the proposed asphalt concrete shall be clean and free of dirt and dust prior to placing a tack coat. Asphalt emulsion shall be used as a tack coat or paint binder on new pavement that is to receive a second lift that has been exposed to traffic or other sources of contaminants or on existing pavements that are to receive an asphalt concrete overlay and also along exposed edges of abutting pavement and concrete curbs and gutters. A tack coat may also be required between subsequent layers of asphalt concrete placed by the contractor when ordered by the City's Construction Inspector. Asphalt emulsion shall conform to Section 92, "Asphalts", of the Caltrans Standard Specifications.

Prior to City acceptance of the improvements (Certificate of Completion), and following the 12 foot straightedge test, and any remove and replace areas with new overlay pavement, streets may be flooded to check for standing water. This procedure may be repeated prior to the expiration of the warranty period. This may be accomplished with a water truck or with rainwater. All low areas in the asphalt concrete pavement holding 0.01-feet for longitudinal and 0.02-feet for transverse depressions or more of water shall be marked by the City's Construction Inspector and milled 0.15-feet and replaced with similar material. A second water test may be necessary at the discretion of the inspector.

A fog or slurry seal may be required at the City's Construction Inspector's discretion following cold planning as described above if it is determined the paving surface is sufficiently irregular, boney, discolored, or unsealed to warrant it.

The Contractor shall schedule paving operations such that at the end of each work shift, each layer of asphalt concrete is placed on all contiguous lanes and shoulders of a traveled way to be opened to public traffic.

At the end of each work shift, the distance between the ends of the layers of asphalt concrete on adjacent lanes shall not be greater than 10 feet nor less than 5 feet. A drop-off of more than 0.15-foot will not be allowed at any time between adjacent lanes open to public traffic.

Additional asphalt concrete shall be placed along the transverse edge at the end of each lane and along the exposed longitudinal edges between adjacent lanes, hand raked, and compacted to form temporary conforms. Kraft paper, or other approved bond breaker, may be placed under the conform tapers to facilitate the removal of the taper when paving operations resume.

Additional asphalt concrete surfacing material shall be place along the edge of the surfacing at private drives, hand raked, if necessary, and compacted to form smooth tapered conforms.

Longitudinal joints in successive pavement lifts shall be offset from lift to lift a minimum of one foot. The surface pass seam shall be located on the lane line. Where extruded concrete curb is removed for pavement widening, Contractor shall grind 1-1/2" of pavement between the nearest lane line and the existing curb and gutter line (including bike lanes). Following placement of the asphalt concrete base lift within the widening section, and 1-1/2" below the new gutter lip, Contractor to replace Petromat fabric or approved equal in grounded area, place asphalt concrete overlay, and restripe and/or replace any delineators removed during the grind.

Prior to permanent patching in a pavement removal area, fresh cutback (temporary pavement) in a minimum thickness of two (2) inches shall be placed as a driving surface.

Whether the surface material is fog sealed or cutback or slurry, the Contractor shall be tenacious in maintaining the surface in a condition and to a grade comparable to the permanent patch. No other materials are allowed as temporary pavement. Placement of steel plates over fresh slurry may be employed per Section 21-2, I. 5. of these Standards.

The temporary surface shall be flush with the surrounding pavement and shall accommodate a smooth drive across it.

Sand and dirt shall not be allowed to accumulate on the slurry surface and adjacent street. It shall be swept daily if necessary.

Utility boxes in asphalt concrete, off-street paths shall include a 12-inch \times 12 inch, concrete collar Type II "minor concrete" as defined in section 71-58 of these standards (Class A, six sack). The top of the collar shall be two inches below the surrounding pavement and the area shall be patch-paved with asphalt concrete as with manholes, water valves and monuments in the street way.

If a bucket or tank or diesel fuel is carried on the paver for the purpose of cleaning rakes and shovels, a container of grease sweep or equivalent absorbent material shall also be carried on the paver. All diesel spills shall be promptly cleaned up.

5) EXISTING PAVEMENT:

- **a.** Cut lines made on existing pavement, both longitudinally and transversely, for the placing of new structural section shall be straight and smooth.
- **b.** Edge grinding (Cold Planning) shall be required where existing asphalt is to be overlayed. The edge grind shall match the depth of the asphalt concrete overlay along the length of the gutter lip and abutting pavement where the asphalt concrete pavement is proposed to conform to the existing pavement.
- **c.** Existing pavements to be overlayed with asphalt concrete shall include the installation of pavement reinforcing fabric in accordance with Section 88, Materials of the Caltrans Standard Specifications at the discretion of the City's Construction Inspector.
- **d.** Existing AC surfaces to remain shall be cut in a straight line parallel to the street centerline, and the exposed edge shall be tracked with SS1H emulsion or equivalent prior to paving. The exposed base material shall be graded and re-compacted per these Construction Standards prior to paving. Graded and recompacted areas shall be approved by the City's Construction Inspector prior to paving.
- e. Where crack sealing is required: Cracks less than ¼ inch in width shall be sealed with SS1-H asphalt emulsion and 30 grit sand. Cracks from ¼ inch to ¾ inch shall be sealed with CRAFCO hot melt rubber sealant or approved equal. Excess sealant shall not extend more than one inch outside the crack onto the pavement surface or above the finished surface of the street. Where cracks larger than ¾ inch (or pavement alligatoring) occur, asphaltic concrete patching may be required at the discretion of the City's Construction Inspector.
- f. Where an excavation in the public right of way is backfilled with two-sack cement slurry per these Construction Standards, the slurry may be brought to the top of the trench until permanent patching. Where rock-saw utility trenching is necessary in the bottom lift of asphalt concrete and prior to placement of top lift of asphalt concrete, the rock saw trench shall be covered with

Glasgrid product (8512, with 100X200 KN tensile strength) or approved equal, at the manufacturers recommendations prior to the placement of top lift of asphalt.

- **g.** If the width of existing pavement between the gutter lip and excavated patch/pave area is three (3) feet or less, all existing pavement between the patch/pave area and the gutter lip shall be removed or milled 0.15 feet in depth, and patched conforming to the adjacent patch/pave area requirements.
- **E. Sound and Retaining Walls** Construction of sound and retaining walls shall conform to the approved plans. The City's Construction Inspector shall inspect all sound and retaining walls shown on the approved subdivision grading or improvement plans. An anti-graffiti coating per Section 71-5 (Materials) and per the manufacturer's recommendations shall be applied to the City side of all sound and retaining walls bounding the City right-of-way or to the side/surface of sound or retaining walls facing public-owned wetlands, open spaces, or parks, at the discretion of the City's Construction Inspector.

The City's Construction Inspector shall be furnished a letter from the applicating contractor certifying that the coating has been applied per the Manufacturer's recommendations, prior to the Certificate of Completion.

The top course of loose block retaining wall such as "Keystone" type shall be epoxied on. The adhesive shall conform to Section 71-5 (Materials) below.

F. Survey Monuments - All survey monuments shall be installed per Detail ST-36. Surface monuments shall be driven flush with the surface of pavement.

Survey monument caps shall be peened and stamped and rebar shall be set at the back of lot prior to the Certificate of Completion.

All rear lot property corners shall be marked with a $\frac{1}{2}$ inch rebar, 12 inches long, and the top flush with finish grade. All lot corners at the street shall be marked with a pneumatically set concrete nail and surveyor's tag, six inches into the back of sidewalk or a sawcut score mark, a minimum of 4 inches long and $\frac{1}{4}$ inch deep, at the back of the City sidewalk or back of curb, whichever applies, or as indicated on the recorded parcel or final map.

G. Street Barricades - All street and sidewalk barricades shall conform to Construction Standard Details ST-31, ST-32, ST-33, and ST-34,

respectively. Sidewalk barricades are required at the termination of all new sidewalk improvements.

- **H. Pavement Removal** Upon demolition of concrete and asphalt concrete pavement, rubble shall be immediately removed or hauled from, and not piled in the City right-of-way. Disposal of such materials shall conform to all local ordinances and regulations of the City of Roseville and the County of Placer relation to land grading, flood plains, drainage facilities and disposal of surplus materials.
- **I. Utility Boxes** Boxes for dry utilities shall not be placed in asphalt concrete pavement, the gutter pan, in driveways or in the lower half of the ramped portion of curb ramps. Utility boxes may be placed in City sidewalk only upon the approval of the City's Construction Inspector.
- **J. Slurry Seal Follow-Up** (For surfacing over asphalt concrete pavement) Upon completion of any slurry seal, all loose, residual material shall be swept up and removed as soon as the slurried area is adequately cured to do so. The surface shall be maintained in a clean condition until such a time as raveling has stopped.
- **K. Detector Loop Related Paving** The minimum total thickness of paving within the area of detector loops is 4 inches. The first lift shall be a minimum three inches, and the second lift (covering the loops) shall be a minimum one-inch.

71-5 MATERIALS

A. Aggregate Base and Subbase - All aggregate base and subbase (AB and ASB) materials shall be Class 2 as specified on the approved improvement plans and shall conform to provisions in Section 26 of the Caltrans Standard Specifications.

Asphalt concrete grindings may be used as AB or ASB provided the Contractor supplies the City written documentation that the material meets the Class 2 specifications.

B. Concrete - All Concrete curbs, curb and gutters, sidewalks, curb ramps, driveways, retaining wall footings, utility box collars, rock wheel trenches and miscellaneous footings shall be constructed of minor concrete conforming to the provisions in Section 90-10, "Minor Concrete," and as described below.

Type II — Modified Portland Cement content of the minor concrete shall be not less than 550 pounds per cubic yard, with a maximum size aggregate not greater than one-inch or smaller than 3/8-inch, except for pothole reconstruction and rock wheel trench backfill, and when

curbs are either extruded or slip-formed, the maximum size aggregate shall be 3/8-inch. For stamped median concrete color, the standard color shall be Davis Style Tile Red #1117, or Scofield Systems, Chromix C-32 Quarry Red, or as approved equal. Apply 60 pounds per 80 square feet in two hand broadcast applications. Contractor may elect to incorporate approved color into concrete mix at 30 pounds of color (intergrally mixed), per cubic yard.

C. Asphalt Concrete - Shall comply with the provisions of Section 39 of the California State Standard Specifications and as modified herewith. The requirements provided within these provisions shall supersede State Specifications where conflicts or other disparities exist.

Asphalt binder shall be performance grade 64-10 paving asphalt conforming to Section 92, "Asphalt," of the Caltrans Standard Specifications.

Asphalt concrete for alley's residential and collector roadways shall be Type A, ½-inch Maximum Medium Gradation, conforming to the requirements of Section 39-2 of the State Standard Specifications.

Asphalt concrete for alley's, residential and collector roadways shall be Type A, ½ inch Maximum Medium Gradation, conforming to the requirements of Section 39-2 of the State Standard Specifications.

Asphalt concrete shall be hot plant mixed and shall be furnished from the plant at a temperature not to exceed 325 degrees F.

- **D. Lime/Fly Ash or Cement Treated Subbase** On a case-by-case basis, lime/fly ash or cement treated subbase may be an acceptable substitute for placement of compacted aggregate base material. Prior to plan approval, the Developer shall submit to the City Engineer for review and approval, a proposal for lime/fly ash or cement treatment sections and compaction procedures, accompanied by recommendations from a California licensed, geotechnical engineer. In no case shall asphalt concrete be placed directly on lime/fly or cement treated bases.
- E. Truncated Domes Truncated dome panels shall be of vitrified polymer composite construction, embedded type, or (surface applied for retrofit applications) manufactured by Armor Tile Tactile Systems, Buffalo, New York, ADA Solutions, N. Billerica, MA, or approved equal. The dimensions and interval of the truncated domes within the panel shall conform to Caltrans Standard Plan RNSP A88 and Division of the State Architect Accessibility Reference Manual, Figure No. 31-23A. The orientation of the dome pattern for all panels shall be parallel with the panel edges.

- **F. Graffiti Coating** –Blok Guard® (Prosoco), Acryli-Master (Graffiti Master), GCP 1000 (Genesis Coatings Inc.), Prmakote 333, by Visual Pollution Technologies or approved equal, non-sacrificial type only.
- **G. Epoxies, Patching Material** Following are products specified for the indicated applications.
 - 1. Bonding extruded curb to asphalt concrete pavement; bonding concrete to existing during pour; bonding the top course of loose block, sound/retaining wall: Burke Epoxy Binder 2104 Type 1 (Supplier: Whitecap), Rezi-Weld 1000, (Supplier: Spec-West), Sealtight Rezi-Weld ER-43 Type I, (Supplier: Spec-West) or approved equal.
 - **2. Anchor Bolts:** Seal Tight Resi-Weld Gel Paste Unitized Cartridge Epoxy (Supplier: Spec West), Covert Operations CIA Gel 7000 (Supplier: White Cap) or approved equal.
 - **3. Patching:** Patchcrete (Supplier: Spec-West), Emaco R350CI Repair Motar (Supplier: White Cap), Ardex CP (Supplier: Spec-West) or approved equal.
- **H. Reinforcement Bar** Rebar shall be grade 60 steel, deformed type. Smooth bar shall not be allowed. All rebar shall be number four (4) unless otherwise specified on the plans.
- **I. Concrete Curing Compound Curing** compound shall conform to ASTM C-309. Type 1-D and Class B, resin base, clear with fugitive red dye. Approved products include Burke Aqua Resin Cure (with dye), W.R. Meadows 1100- Clear Series (with dye) or approved equal.
- **J. Slurry Seal** Slurry seal shall conform to Caltrans Specifications, Section 37-2, and Type 2. A design mix shall be submitted to the Development Section for approval prior to commencing work.