



**Public Works
Engineering**
311 Vernon Street
Roseville, California 95678-2649

October 11, 2013

Re: 2012 Slurry Seal Project Warranty Work

Dear Resident:

The Contractor that placed the resurfacing treatment in your neighborhood will be performing repair work at various locations in your neighborhood. The repair work is scheduled to begin this week and continue for two weeks after work has begun. Although not anticipated, this tentative schedule may be subject to change due to material availability, weather conditions, and/or equipment breakdown. The Contractor will inform you of the specific work dates by posting an advance notice door hanger at your residence. "No Parking" barricades will also be placed on the street a minimum of 48 hours prior to the scheduled construction. The tentative schedule is also posted on the City of Roseville web site at: <http://www.roseville.ca.us/road>

The Contractor will be placing an additional surface treatment of Microsurfacing over areas in need of repair. The Microsurfacing application is a mixture of small aggregate, asphalt, and water. Microsurfacing is applied as a liquid material that hardens as the material cures. Initial curing takes approximately 1 to 2 hours and the Microsurfacing will continue to cure over the next six to eight weeks.

During the day of the work, you will not be able to park or drive your vehicles on the street between 8:00 AM and 6:00 PM. "No Parking" signs will be posted 48 hours prior to the work date. The work being done will be performed on portions of the street and some locations will be full street width sections. To avoid oil spray and allow us to treat and clean the entire pavement surface, we request that you park your vehicles in your driveway or on an adjacent street that is not being resurfaced. If you need to use your vehicle, we recommend that you move your vehicle before 8:00 AM to an adjacent street that is not being resurfaced.

Please be advised that the application of the Microsurfacing can take between four to six hours to complete. During this time, your street may be closed to all vehicle traffic or traffic control devices will be in place to show areas of work where driving is not permitted. After the surface treatment has cured, the street will be reopened to traffic. When the street is reopened, please drive slowly; there will be loose gravel on the street.

Also, as the surface treatment continues to cure, loose gravel will shed from the roadway surface. This is normal and will decrease over time. The Contractor is required to sweep the streets to remove the loose gravel. **If there is excessive loose gravel on the roadway, please call (916) 746-1300.** We will inspect the street and resolve any problems as quickly as possible.

(continued on back)

We wish to call to your attention the following precautions:

- Do not drive on the surface treatment until the streets have been reopened to traffic.
- We recommend that you continue to park your car in your driveway until the sweeping is completed.
- Check your shoes before walking into your house. The loose gravel can be picked up and tracked onto carpets or scratch wood floors.

Occasionally, some streets are scheduled to be resurfaced on the same day of refuse collection. If this occurs, please put your trash bin out, as normal, the night before your scheduled refuse pick up day. After the refuse trucks have emptied the bins, the Contractor will move any bins that are on the roadway to the adjacent driveway.

If you have additional questions, or need assistance with accessing your home during construction activities please call the Engineering Division at (916) 782-ROAD (7623) or the Street Maintenance Division at (916) 774-5790.

Thank you for your cooperation.